

# Client: Whiting Oil and Gas

Locations: Fracking Pond A & B  
New Raymer, CO

## BENCHMARK HIGHLIGHTS

Scope/Summary – There was no site power for pump station at fracking ponds. We installed an 18KV genset with load bank at pond A and a 15KV genset with load bank at pond B to provide site power for 4-7 MGD pump stations. Both are equipped with ATS switches to change from primary to secondary power source.



- Site Lighting



- Conduit install
- Grounding
- Testing and commissioning
- Pond A - 800 Amp Primary Disconnect
- Pond B - Install 600 Amp Disconnect for generator power and a 400 Amp Disconnect for load bank testing.

## Benchmark Project Management

- Dave Aguiar – PM
- Superintendent – Mike Stephens

## Notable Features

- Pump stations
- Fracking water supply ponds

## Reference/Owner

Whiting Oil and Gas  
Contact: Tate Wammen  
Phone: 970-380-0243

## Completion Date:

July 2014 – Ongoing supplemental work



Benchmark Electrical Solutions  
1204 West Ash Street, Unit J  
Windsor, CO 80550  
P 970-229-1885  
F 970-229-1895